

City of Mount Vernon, Ohio

Belmont Ave. & N. Mulberry St. Reconstruction (CDBG) Project

Addendum No. 1 3/23/2020

This addendum addresses the following issues:

Bid Sheets

- Deleted duplicate Ref. items, moved stop bar and crosswalk striping down to Option 1.
- Corrected Option 1 designations.
- Removed unit costs and item costs.
- Changed item number to 252 for Full Depth Asphalt Pavement Repair, As Per Plan (6" depth, post mill)
- Renumbered Ref. items

Brian W. Ball, P.E.
City Engineer

40 Public Square
Mount Vernon, OH 43050
(740) 393-9528

BID SHEET
CITY OF MOUNT VERNON, KNOX COUNTY, OHIO
Belmont & N. Mulberry Improvements

Ref.	Item No.	Description	Quantity	Units	Unit Cost	Item Cost
1	201	Clearing and Grubbing	1	L.S.		
2	202	Ex. Gravel Drive Removed	525	S.Y.		
3	202	Ex. Asphalt Pavement Removed (Alley's & Driveways)	490	S.Y.		
4	202	Ex. Concrete Drive Removed	300	S.Y.		
5	202	Ex. Concrete Sidewalk Removed	1,900	S.Y.		
6	202	Ex. Concrete Curb Removed	3,000	L.F.		
7	202	Ex. 12 in. Storm Sewer Pipe Removed	565	L.F.		
8	202	Ex. Storm Catch Basin Removed	10	EA.		
9	202	Ex. 6 in. Ductile Iron Pipe Removed	45	L.F.		
10	202	Ex. 6 in. Valve Adjusted to Grade	1	EA.		
11	202	Ex Mailbox Removed & Relocated	1	EA.		
12	202	Ex. Retaining Wall Removed	70	L.F.		
13	203*	Excavation	250	C.Y.		
14	203*	Embankment	250	C.Y.		
15	204	Subgrade Compaction	3,000	S.Y.		
16	304	Aggregate Base (T=4-in), Sidewalk and Drives	400	C.Y.		
17	452	Non-Reinforced Concrete Pavement, T=6-in, Class QC 1	1,100	S.Y.		
18	452	Non-Reinforced Concrete Pavement, T=8-in, Class QC 1	250	S.Y.		
19	608	Curb Ramp with Detectable Warning (2-ft x 4-ft)	17	EA.		
20	608	Concrete Walk	14,925	S.F.		
21	609	24" Concrete Curb and Gutter (Type 2 Modified), Class QC 1	3,300	L.F.		
22	609	24" Concrete Curb and Gutter (Type 3 Mountable) Class QC 1	3,800	L.F.		
23	611	12-in Storm Conduit , PP-Type B	390	L.F.		
24	611	15-in Storm Conduit , PP-Type B	555	L.F.		
25	611	18-in Storm Conduit , PP-Type B	240	L.F.		
26	611	Catch Basin, W/Mountable Curb Grate	16	EA.		
27	611	Catch Basin, W/Standard Grate	1	EA.		
28	611	Manhole, MH-1.2	3	EA.		

BID SHEET
CITY OF MOUNT VERNON, KNOX COUNTY, OHIO
Belmont & N. Mulberry Improvements

Ref.	Item No.	Description	Quantity	Units	Unit Cost	Item Cost
29	614	Maintaining Traffic	1	L.S.		
30	623	Construction Layout Stakes and Surveying	1	L.S.		
31	624	Mobilization	1	L.S.		
32	659	Seeding and Mulching (Vegetation Establishment)	1	L.S.		
33	832	Sediment and Erosion Control	1	L.S.		
34	Spec	Bond	1	L.S.		
BELMONT & N. MULBERRY IMPROVEMENTS - TOTAL COST						
OPTION #1 Mulberry St. & Belmont Ave. Resurfacing						
35	624	Mobilization	1	L.S.		
36	252*	Full Depth Asphalt Pavement Repair, As Per Plan (6" depth, post mill)	410	S.Y.		
37	254	Pavement Planing, Asphalt Concrete (T=3-in)	8,150	S.Y.		
38	301	Asphalt Concrete Base, PG64-22 (T=6-in Trench Repair)	30	C.Y.		
39	407	Rubberized Tack Coat, per ODOT CMS 702.13 (0.1 Gal./S.Y.)	820	Gal.		
40	441	Asphalt Concrete, Surface Course, Type 1, PG64-22 (T=1.25-in)	290	C.Y.		
41	441	Asphalt Concrete, Intermediate Course, Type 1, PG64-22 (T=1.75-in)	400	C.Y.		
42	642	Stop Bar, W=12-in	35	L.F.		
43	644	Crosswalk Striping, W=12-in	405	L.F.		
OPTION #1- N. MULBERRY ST. & BELMONT AVE. TOTAL COST						
OPTION #1 - SHELLMAR PARK PARKING LOT						
44	201	Mobilization	1	LS		
45	203	Excavation-For Parking Lot	1	LS		
46	304	304 aggregate base (6")	126	CY		
47	407	Tack Coat @ .10 Gal/SY	152	GAL		
48	441	2.5- Inch asphalt Intermediate course, - Type 2,	53	CY		
49	441	1 1/2- Inch asphalt concrete surface course, - Type 1, (441) (PG64-22) City Spec	32	CY		
50	644	Word On Pavement, (Handicap Symbol)	2	EA		
51	644	Parking Stall Line, 4" White	800	LF		
OPTION #1 - SHELLMAR PARK PARKING LOT - TOTAL COST						

BID SHEET
CITY OF MOUNT VERNON, KNOX COUNTY, OHIO
 Belmont & N. Mulberry Improvements

Ref.	Item No.	Description	Quantity	Units	Unit Cost	Item Cost
OPTION #1 - SHELLMAR PARK BASKETBALL COURT						
52	201	Mobilization	1	LS		
53	203	Excavation-For Court	1	LS		
54	304	304 aggregate base (8")	164	CY		
55	407	Tack Coat @ .10 Gal/SY	150	GAL		
56	441	2 1/2- Inch asphalt Intermediate course, - Type 2,	51	CY		
57	441	1 1/2- Inch asphalt concrete surface course, - Type I, (441) (PG64-22) City Spec	31	CY		
OPTION #1 - SHELLMAR PARK BASKETBALL COURT - TOTAL COST						

*DENOTES CONTINGENCY ITEM, AS DIRECTED BY THE ENGINEER
 SPEC - REFER TO PLAN NOTES, DETAILS & SUPP SPECS

COMPANY NAME: _____

DATE: _____

